



Town of Dundee
RFP 16-02 – Hwy. 27 S. Lift Station Rehabilitation
Addendum #1

To All Potential Bidders: This addendum is issued to modify the previously issued bid documents and/or given for informational purposes, and is hereby made a part of the bid documents.

Based on the Project Scope and Scope Price of RFP 16-02, the Town is requesting a price of the total project to be submitted in lieu of the Lump Sum Bid (page 28) in the RFP document.

Questions

- When will Omni Site be delivered?
It was purchased the last week of April/first week of May, so it should be delivered by the end of the month.
- Is the start-up and communication included in the Town's price, concerning OmniSite?
Yes, it is included.
- Does the entire control panel need to be purchased by contractor?
Yes.
- Will risers/bases be replaced?
Yes, and plates will be needed for the bases.
- Can the contractor make a recommendation to put in fiberglass liners?
Yes.
- Is the contractor responsible for surveying the property?
No, the Town will survey the property. The surveyor will give the points to Town, so the Town can mark them.
- Where is the Town easement? Fence? Property expansion to address electrical box?
The Town is awaiting this information.
- The concrete posts are splitting. Does the Town want a whole new electrical rack?
Yes, the Town wants a new rack.
- Does the pipe disconnect need to be updated?
Yes.
- Does Town want the pipe disconnect to be put back to 4 in.?
Yes, and rebar and seams need to be sandblasted/painted.
- Is there water on site?
Yes. The Town needs to put in RPZs or backflow.



- Size of pipes?
The pipes are 6 inches.
- What is the depth of the well?
The depth of the well is 14 ft., with a diameter of 6 ft.
- Is the Town requesting the piping to be redone?
Please quote both options.