



**TOWN OF DUNDEE**  
**RFP 26-02 DUNDEE COMMUNITY CENTER**  
**PARKING LOT RESURFACING PROJECT**  
**ADDENDUM #2**

**Q: What is the thickness of the mill?**

**A:** Will be a 1-inch mill for this project where possible other areas might need to be no more than 1/2in due to lack of asphalt material currently in place. (millings will be kept by TOWN OF DUNDEE).

**Q: What do you want to put down, 1 1/2”?**

**A:** 1 1/2 - inch of asphalt for resurface that will allow for a 1/4 - inch overlay on curb lines.

**Q: When you widen the spot, will you want to do a pole?**

**A:** For new purposed widening of parking spots for handicap parking Town staff will perform all work to prep for width needed to create the handicap parking spaces and supply all signage for project. Contractor will only pave the areas. (this will only take place if awarded contractor agrees that it needs to be done to meet ADA requirements).

**Q: Does the spot on the west side before the awning hold water?**

**A:** Yes, staff will create drainage for this area before the project starts

**Q: Are you looking for us to remove the concrete sidewalk and reconfigure the parking spots and redo it for the sidewalk between the handicap spots?**

**A:** Town staff will remove concrete sidewalk that intrudes into the parking lot, the contractor will pave the area to create parking spaces to be ADA compliant.

**Q: If we had to extend the handicap stalls, are you looking to extend out the S curb?**

**A:** No staff will install the curb at a late date and time.

**Q: Do you have the Davis Bacon wage information?**

**A:** Yes, that was provided at the mandatory pre-bid meeting as part of addendum #1 package.